

Hull Academy, Hull

Who:

Hull City Council
National Academic Framework

What:

Stormwater attenuation

Specifier:

RAMBOLL

Main contractors:

Balfour Beatty

Drainage subcontractor:

MOORTOWN



Hull
City Council

Project details

Project requirements:

Four variable size tanks with pumping stations to rising main.

Total project cost:

£48 million

Key criteria:

Speed and ease of installation to fit complex project schedule, replacing Pickering High School and creating co-location with Ganton Special School and further facilities in support of Sirius Academy, including sports hall, multi-use games areas and 3G sports pitch.

Solution achieved:

Four tanks across the site, the three larger tanks forming a 12 leg manifold for compactness, and all tanks fitted at each end with access shafts for easy inspection and maintenance. Tanks 1 and 2 fitted complete in just 4 and then 3 weeks..

Other benefits:

Convenience, performance and providing a package which the project contractors reported as hard to beat - a fully designed and equipped system which can be adapted if conditions demand, with good advice and support and a smooth rhythm to installation.



Tubosider United Kingdom Ltd
10 Sutton Fold Industrial Estate,
Off Lancots Lane,
Sutton.
St Helens. WA9 3GL

Supporting you from the ground up.

Call us: 01744 452 900
Email us: info@tubosider.co.uk
Visit us: www.tubosider.co.uk