

## Hull Academy, Hull

**Who:**

Hull City Council  
National Academic Framework

**What:**

Stormwater attenuation

**Specifier:**

**RAMBOLL**

**Main contractors:**

**Balfour Beatty**

**Drainage subcontractor:**

**MOORTOWN**



**Hull**  
City Council

### Project details

**Project requirements:**

Four variable size tanks with pumping stations to rising main.

**Total project cost:**

£48 million

**Key criteria:**

Speed and ease of installation to fit complex project schedule, replacing Pickering High School and creating co-location with Ganton Special School and further facilities in support of Sirius Academy, including sports hall, multi-use games areas and 3G sports pitch.

**Solution achieved:**

Four tanks across the site, the three larger tanks forming a 12 leg manifold for compactness, and all tanks fitted at each end with access shafts for easy inspection and maintenance. Tanks 1 and 2 fitted complete in just 4 and then 3 weeks..

**Other benefits:**

Convenience, performance and providing a package which the project contractors reported as hard to beat - a fully designed and equipped system which can be adapted if conditions demand, with good advice and support and a smooth rhythm to installation.



Tubosider United Kingdom Ltd  
10 Sutton Fold Industrial Estate,  
Off Lancots Lane,  
Sutton.  
St Helens. WA9 3GL

**Supporting you from the ground up.**

Call us: 01744 452 900  
Email us: info@tubosider.co.uk  
Visit us: www.tubosider.co.uk